

Arrow Platform

Network Topology



Arrow models costs associated with building FTTP networks








Arrow FTTP Network Model Topology



- (A) **Central Office** – Hub of local loop connections
- (B) **Splice Point** – Location where possible to splice new fiber off of existing fiber strands
- (C) **Fiber Distribution Hub** – Splits fiber at the junction between “feeder” and “distribution”
- (D) **Fiber Distribution Terminal** – Splits fiber at the junction between “distribution” and “customer drop”
- (E) **Success-Based Capex** – Equipment and labor costs associated with connecting a customer; includes drop, ONT, and other hardware and installation at the customer premises
- (F) **Multi-Dwelling Unit** – Variable equipment and labor costs associated with connecting units in a MDU
- (G) **Fiber** – Fiber costs can be assigned by location: aerial, underground (*usually located in urban conduit*), and buried (*dug in shallow trench*)

Input values may be varied by morphology/location


Fiber costs drive the largest capex deployed in a plan; splice points and success-based capex are also important factors

	Arrow Input	Description	Received	Impact on Plan Financials
Ordered by model impact	G	Fiber Costs	Fiber costs can be assigned by morphology and by location: aerial, underground (<i>usually located in urban conduit</i>), and buried (<i>dug in shallow trench</i>); includes materials and labor	<div style="border: 1px solid black; padding: 5px; display: inline-block;"> In past Arrow analysis, fiber costs have accounted for the majority of plan capex </div> 
	B	Splice Points	Location where possible to splice new fiber off of existing fiber strands; splice point locations have a significant effect on fiber routing	
	E	Success-Based Capex	Equipment and labor costs associated with connecting a customer; includes drop, ONT, and other hardware and installation at the customer premises	
	C	Fiber Distribution Hub	Splits fiber at the junction between "feeder" and "distribution"	
	D	Fiber Distribution Terminal	Splits fiber at the junction between "distribution" and "customer drop"	
	A	CO Upgrade Cost	Hub of local loop connections; upgrade costs include installing and upgrading equipment for GPON	
	F	MDU	Variable equipment and labor costs associated with connecting units in a MDU	

Sources: Altman Solon Knowledgebase

Low  → High 


While FTTP and FTTN network deployments use similar general architectures, there are a few key differences around connecting prems



FTTN Deployment

(assumes node is in range of prems to guarantee 25Mbps target speed)

- A FTTN network deployment lays fiber from the CO to remote terminals in sufficient range to guarantee a 25Mbps target speed for each connected prem
- The network uses Remote Terminal (RT) equipment at network end nodes
- When a prem subscribes, connect cost is assumed to cover both equipment and installation




FTTP Deployment

(fiber is built to the prem doorstep and can offer 100Mbps+ speeds)

- A FTTP network deployment lays fiber from the CO all the way to the doorstep, guaranteeing speeds over 100Mbps for each connected prem
- The network uses FDHs and FHTs / MDU equipment to pass all prems
- This is a more capex intensive deployment compared to FTTH since it requires additional fiber miles and equipment
- When a prem subscribes, higher connect cost is assumed, given the different CPE required

Arrow models costs associated with the following FW network topology

Arrow FW Network Model Topology



- 1 **Central Office** – Hub of local loop connections
- 2 **Splice Point** – Location where possible to splice new fiber off of existing fiber strands
- 3 **5G Fixed Wireless Node** – Access Node and tower for 5G signal; associated costs include equipment, labor
- 4 **Spectrum** – Bands of frequencies for propagating wireless information; radius (propagation distance) can be a model input
No costs associated with spectrum in Arrow
- 5 **Obstacles** – Foliage and buildings can impede the propagation of high-frequency wireless signals
- 6 **Success-Based Capex** – Equipment and labor costs associated with connecting a customer; includes hardware and installation at the customer premises
- 7 **Multi-Dwelling Unit** – Variable equipment and labor costs associated with connecting units in a MDU
- 8 **Fiber** – Fiber costs can be assigned by location: aerial, underground (*usually located in urban conduit*), and buried (*dug in shallow trench*)

Input values may be varied by morphology/location

Spectrum propagation and fiber costs drive most capex in a fixed wireless build plan; splice points and success-based capex also important factors

Arrow Input	Description	Received	Impact on Plan Financials
4 5 Spectrum Radius, Obstacles	Propagation distance of wireless signal		
8 Fiber Costs	Fiber costs can be assigned by morphology and by location: aerial, underground (<i>usually located in urban conduit</i>), and buried (<i>dug in shallow trench</i>)		
3 5G Fixed Wireless Node Cost	Access Node and tower for 5G signal; associated costs include equipment, labor		
2 Splice Points	Location where possible to splice new fiber off of existing fiber strands; splice point locations have a significant effect on fiber routing		
6 Success-Based Capex	Equipment and labor costs associated with connecting a customer; includes hardware and installation at the customer premises; based on % prems requiring truck roll		
1 CO Upgrade Cost	Hub of local loop connections; upgrade costs include installing and upgrading equipment for GPON		
7 MDU	Variable equipment and labor costs associated with connecting units in a MDU; can MDUs be served with FW?		

Ordered by model impact

Sources: Altman Solon Knowledgebase

Low → High

Wireless node placement software uses the following methodology

1

Determine Set of Potential Site Locations

Potential site types consist of:

- Existing structures
- Existing client sites
- New sites

Each site type has different costs associated with it

2

Estimate Rate Reach Curves for Potential Sites

NASA has 30m x 30m data on:

- Foliage density
- Clutter density

Based on this data, Arrow can estimate impedance near site and **calculate a rate reach boundary***

3

Optimally Place Nodes for 100% Coverage

Begin by placing nodes in lowest capex/prem-passed locations, based on:

- Coverage (# of households)
- Costs (site type)

Continue placing nodes until 100% coverage for geography is reached

4

Forecast Detailed Cash Flow for All Nodes

Calculate detailed cash flow for each of the sites placed in step 3 based on:

- Site CapEx (site type, morphology)
- Penetration (competition)
- Incremental CPGA
- ARPU
- CCPU
- Sub lifetime

5

Route Fiber and Prune Low IRR Nodes

Route fiber to all nodes in the 100% coverage placement

Leverage pruning engine to **sequentially remove nodes until IRR or budget constraint is met**

- Decision to prune is based on capex of fiber as well as detailed cash flow projections from previous step

6

Calculate Overall Scenario Financials

Calculate scenario financials for pruned scenario incorporating:

- Site CapEx
- Fiber CapEx (or OpEx)
- Subscriber Revenue, OpEx
- Cash Flow

*Not intended to replace detailed RF designs but highly effective to accelerate planning purposes